



SIDE ELEVATION
SCALE 1/8"=1'-0"



SIDE ELEVATION
SCALE 1/8"=1'-0"

Approved fire retardant-rated wood roof sheating 4' each side of common wall




5547 SUNDOWN PLACE NW
ROCHESTER MN 55901
LOT 5, BLOCK 1, HARVEST WEST
HVW-001-051

FRONT ELEVATION
SCALE 1/4"=1'-0"

5543 SUNDOWN PLACE NW
ROCHESTER MN 55901
LOT 6, BLOCK 1, HARVEST WEST
HVW-001-061

Approved fire retardant-rated wood roof sheating 4' each side of common wall



5543 SUNDOWN PLACE NW
ROCHESTER MN 55901
LOT 6, BLOCK 1, HARVEST WEST
HVW-001-061

5547 SUNDOWN PLACE NW
ROCHESTER MN 55901
LOT 5, BLOCK 1, HARVEST WEST
HVW-001-051

REAR ELEVATION
SCALE 1/4"=1'-0"


BIGELOW HOMES
4057 28TH STREET NW #100
BUILDER LICENSE # BC-431673

THESE DRAWINGS HAVE BEEN PREPARED USING INFORMATION PROVIDED BY THE CUSTOMER/CONTRACTOR WHO IS SOLELY RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION PROVIDED. THE DRAWINGS ARE NOT A SUBSTITUTE FOR PERMIT DRAWINGS PREPARED BY A CONTRACTOR OR ARCHITECT THAT ARE ESTABLISHED TO COMPLY WITH LOCAL BUILDING CODES AND PRACTICES. BEFORE STARTING CONSTRUCTION, THE CUSTOMER SHOULD CONSULT A CONTRACTOR OR ARCHITECT TO DETERMINE IF THE DRAWINGS NEED TO BE CHANGED TO SATISFY: 1.) STATE OR LOCAL BUILDING CODES OR REGULATIONS, 2.) SITE CONDITIONS, 3.) LOCAL CONSTRUCTION PRACTICES, AND 4.) OTHER FACTORS. WE RECOMMEND THAT YOU CONSULT LOCAL BUILDING OFFICIALS TO DETERMINE IF A BUILDING PERMIT IS REQUIRED. WE ASSUME NO RESPONSIBILITY FOR ANY ERRORS, OMISSIONS, DEFICIENCIES, IMPROPER CONSTRUCTION, OR DEFECTS OF THE DRAWINGS.

ACKNOWLEDGED BY: CUSTOMER/CONTRACTOR SIGNATURE DATE

CONTRACTOR: BIGELOW HOMES
OWNER: HARVEST WEST MASTER PLAN #20-12

DRAWN BY:	MJP
DATE:	10/19/26
SQ. FT.	NOTED
SCALE:	NOTED
SHEET:	A01
BIGELOW HOMES	



1,394 SQ.FT.

5547 SUNDOWN PLACE NW
ROCHESTER MN 55901
LOT 5, BLOCK 1, HARVEST WEST
HVW-001-051

5543 SUNDOWN PLACE NW
ROCHESTER MN 55901
LOT 6, BLOCK 1, HARVEST WEST
HVW-001-061

1,394 SQ.FT.

DISCRIPTION: MAIN FLOOR DATE:

BRACED PANEL LENGTH TABLE
BASED ON WIND SPEED (<115mph)

* ADJUSTMENT CALCULATION EXAMPLE: BRACED WALL LINE LENGTH x EXPOSURE FACTOR = ROOF TO EAVE TOTAL; WALL HIGHT TOTAL x ROOF TO EAVE TOTAL = NUMBER BRACED WALL LINES; REQUIRED BRACING LENGTH (FEET) = PROVIDED BRACING LENGTH

BRACED WALL LINE	BRACING METHOD TABLE R602.10.4.1	BRACED WALL LINE SPACING	REQUIRED BRACING LENGTH (FEET)	EXPOSURE FACTOR CONDITION	ROOF TO EAVE TOTAL	WALL HIGHT TOTAL	NUMBER BRACED WALL LINES	REQUIRED BRACING LENGTH (FEET)	PROVIDED BRACING LENGTH
Ⓐ	CS-WSP	27 FT.	4.2'	1.0	1.1	0.95	1.6	7.1'	10.5'
Ⓑ	CS-WSP	27 FT.	4.2'	1.0	1.1	0.95	1.6	7.1'	10.8'
Ⓒ	CS-WSP	15 FT.	2.8'	1.0	1.1	0.95	1.6	4.7'	6.5'
Ⓓ	CS-WSP	9 FT.	2.0'	1.0	1.1	0.95	1.6	3.4'	6.0'
Ⓔ	CS-WSP	12 FT.	2.3'	1.0	1.1	0.95	1.6	3.9'	7.5'

DISCRIPTION: MAIN FLOOR DATE:

BRACED PANEL LENGTH TABLE
BASED ON WIND SPEED (<115mph)

* ADJUSTMENT CALCULATION EXAMPLE: BRACED WALL LINE LENGTH x EXPOSURE FACTOR = ROOF TO EAVE TOTAL; WALL HIGHT TOTAL x ROOF TO EAVE TOTAL = NUMBER BRACED WALL LINES; REQUIRED BRACING LENGTH (FEET) = PROVIDED BRACING LENGTH

BRACED WALL LINE	BRACING METHOD TABLE R602.10.4.1	BRACED WALL LINE SPACING	REQUIRED BRACING LENGTH (FEET)	EXPOSURE FACTOR CONDITION	ROOF TO EAVE TOTAL	WALL HIGHT TOTAL	NUMBER BRACED WALL LINES	REQUIRED BRACING LENGTH (FEET)	PROVIDED BRACING LENGTH
①	CS-WSP	38 FT.	5.7'	1.0	1.1	0.95	1.45	8.7'	15.5'
②	CS-WSP	12 FT.	2.3'	1.0	1.1	0.95	1.45	3.5'	6.0'
③	CS-WSP	22 FT.	3.7'	1.0	1.1	0.95	1.45	5.6'	8'
④	GB	38 FT.	11.9'	1.0	1.1	0.95	1.45	18'	18'

WALL BRACING NOTES: CS-WSP

1. ALL WALLS SHALL BE CONTINUOUSLY SHEATHED WITH WOOD STRUCTURAL PANELS
2. CS-WSP ON PLANS INDICATE AREAS OF BRACED PANELS
3. BRACED PANELS SHALL BE CONSTRUCTED WITH 24" O.C. STUDS. TOP PLATE FASTENED TO SOLID FRAMING WITH 8d NAILS 6" O.C.
BOTTOM PLATES FASTENED TO SOLID FRAMING W/ 3-16d NAILS 16"O.C.
7/16" OSB SHEATHING (24/16 INDEX) FASTENED W/ 8d COMMON NAILS 6"O.C. ON EDGES AND 12" O.C. IN FIELD.
SOLID BLOCKING BETWEEN TRUSSES WITH HEEL GREATER THAN 9-1/4" TO WITHIN 2" OF ROOF SHEATHING FASTENED WITH MIN 8d NAILS 6" O.C. ALONG LENGTH OF PANEL
4. ANY OTHER TYPE OF BRACING METHOD SHALL BE INDICATED ON PLAN AND SEPARATE DETAIL WILL BE PROVIDED.

BIGELOW HOMES
4057 28TH STREET NW #100
BUILDER LICENSE # BC-431673

THESE DRAWINGS HAVE BEEN PREPARED USING INFORMATION PROVIDED BY THE CUSTOMER/CONTRACTOR WHO IS SOLELY RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION PROVIDED. THE DRAWINGS ARE NOT A SUBSTITUTE FOR PERMIT DRAWINGS REQUIRED BY LAW/OTHER AUTHORITIES AND ARE NOT INTENDED TO BE USED FOR CONSTRUCTION. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT THE DRAWINGS COMPLY WITH ALL APPLICABLE LOCAL BUILDING CODES AND PRACTICES. BEFORE STARTING CONSTRUCTION, THE CUSTOMER SHOULD CONSULT A CONTRACTOR OR ARCHITECT TO DETERMINE IF A BUILDING PERMIT IS REQUIRED. THE DRAWINGS MAY NEED TO BE CHANGED TO SATISFY LOCAL BUILDING CODES OR REGULATIONS. IF PERMIT DRAWINGS ARE REQUIRED, THE CUSTOMER SHOULD CONSULT A CONTRACTOR OR ARCHITECT TO DETERMINE IF A BUILDING PERMIT IS REQUIRED. WE ASSUME NO RESPONSIBILITY FOR ALL OR DAMAGES ARISING FROM ERRORS, OMISSIONS, DEFICIENCIES, IMPROPER CONSTRUCTION, OR DEFECTS OF THE DRAWINGS.

ACKNOWLEDGED BY: CUSTOMER/CONTRACTOR SIGNATURE DATE

CONTRACTOR: BIGELOW HOMES
HARVEST WEST MASTER PLAN #20-12
OWNER:

DRAWN BY:	MJP
DATE:	10/9/26
SQ. FT.	NOTED
SCALE:	NOTED
SHEET:	A03


BIGELOW HOMES

VENTILATION:
ERV SHALL BE INSTALLED TO MEET THE REQUIREMENT OF A BALANCED VENTILATION SYSTEM

INSULATION:

CEILING:	BLOWN FIBERGLASS	R-50
ABOVE GRADE WALLS:	FIBERGLASS BATTS	R-21
FOUNDATION:	2" RIDGID FOAM	R-10


PASSIVE RADON SYSTEM
A MINIMUM 3" DIAMETER PIPE WILL BE INSTALLED THAT ATTACHES TO A "T" FITTING ON THE INSIDE DRAIN TILE AND RUN UP THROUGH THE BUILDING FLOORS AND TERMINATE AT LEAST 12" ABOVE THE SURFACE OF THE ROOF IN A LOCATION AT LEAST 10' AWAY FROM ANY WINDOW OR OTHER OPENING INTO THE CONDITIONED SPACES OF THE BUILDING THAT IS LESS THAN 2' BELOW THE EXHAUST POINT, AND 10' FROM ANY WINDOW OR OTHER OPENING IN AJOINING OR ADJACENT BUILDINGS. THE PIPE WILL BE INSTALLED TO PROVIDE POSITIVE DRAINAGE TO THE GROUND BENEATH THE SLAB OR SOIL-GAS RETARDER. RADON VENT PIPES SHALL PROVIDE ENOUGH SPACE AROUND THE PIPE FOR FUTIRE INSTALLATION OF A FAN SYSTEM. THE SPACE PROVIDED FOR THE INSTALLATION OF A FUTURE FAN SHALL BE MINIMUM OF 24" IN DIAMETER, CENTERED ON THE AXIS OF THE VENT SHAFT, AND SHALL EXTEND FOR A MINIMUM VERTICAL DISTANCE OF 36". AN APPROVED ELECTRICAL OUTLET SHALL BE INSTALL NEAR THIS SPACE. ALL RADON VENT PIPES SHALL DE IDENTIFIED WITH AT LEAST ONE LABEL ON EACH FLOOR AND IN ACCESSIBLE ATTICS. THE LABEL SHALL READ "RADON REDUCTION SYSTEM". RADON PIPES ROUTED THROUGH UNCONDITONED SPACE SHALL BE INSULATED WITH R-4 INSUL.




CS-PF METHOD
NOT TO SCALE

WINDWASH BARRIER:


- AT EXTERIOR EDGE OF ATTIC INSULATION. A MINIMUM OF 1" OF AIR SPACE SHALL BE PROVIDED BETWEEN INSUL AND SHEATHING.



ALL WINDOWS WILL BE ANDERSEN 100 SERIES WITH A U-VALUE NOT TO EXCEED .32



SHEATHING FASTENED WITH 8d COMMON NAILS 6" O.C. EDGE AND 12" O.C. FIELD




STEM WALL REINFORCEMENT

EACH SIDE OF THE GARAGE DOOR WHERE BRACED WALL PANELS ATTACH

CEILING:

- 5/8" SHEET ROCK
- 6 MIL POLY
- BLOWN INSULATION R-49

WOOD SILL PLATES SHALL BE ANCHORED TO THE FOUNDATION WITH ANCHOR BOLTS SPACED A MAXIMUM OF 6 FEET ON CENTER



FOAM COVERED WITH 6-MIL POLY SLIP SHEET AND HAVE RIGID, OPAQUE, AND WEATHER RESISTANT PROTECTIVE COVERING OVER EXPOSED INSULATION EXTENDING MINIMUM 6" BELOW GRADE

THIS HOME WILL BE BUILT USING ADVANCED WALL FRAMING. ALL EXTERIOR WALLS ON THE HOUSE WILL BE 2X6 24" O.C. WITH 2 STUD CORNERS.

EXTERIOR WALL:

SIDING NOTED ON ELEVATIONS
7/16" OSB SHEATHING
2X6 STUDS 24" O.C.
5-1/2" F.F. INSULATION R-20
6 MIL POLY PERM VAPOR BARRIER TAPED @ JOINTS
1/2" SHEET ROCK


EAVE SYSTEM:

2X6 SUBFASCIA
ALUMINUM FASCIA
2X4 LOOKOUTS 24" O.C.
ALUMINUM SOFFIT W/CANT VENT
AIR CHTUES 48" O.C.


MAIN FOUNDATION:
16"X8" CONC FOOTING
4-CRS 8" CONC BLOCK
1-CRS 6" CONC BLOCK
1/2"X10" ANCHOR BOLTS 6' MAX O.C. SPACING
12" FROM END OF EACH PLATE
2X6 .40 TRTD BOTTOM PLATE.
CLOSED CELL SILL SEAL

ROOF SYSTEM:

ENERGY TRUSSES 24" O.C. SPECS BY MFG.
1/2" OSB ROOF SHEATHING P.I.I. 32/16
WINTERGUARD APPLIED SHINGLE FASHION FROM EAVES TO A POINT 24" INSIDE EXTERIOR WALL.
1 LAYER 15 # FELT ON REMAINING
30 YEAR ASPHALT SHINGLES



2-STUD CORNER WITH DRYWALL CLIPS
GreenBuildingAdvisor.com



INTERIOR INTERSECTING WALL WITH DRYWALL CLIPS
GreenBuildingAdvisor.com

BIGELOW HOMES
4057 28TH STREET NW #100
ROCHESTER, MN 55901
BUILDER LICENSE # BC-431673


THESE DRAWINGS HAVE BEEN PREPARED USING INFORMATION PROVIDED BY THE CUSTOMER/CONTRACTOR WHO IS SOLELY RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION PROVIDED. THE DRAWINGS ARE NOT A SUBSTITUTE FOR PERMIT DRAWINGS PREPARED BY A CONTRACTOR OR ARCHITECT AND MAY NOT MEET NORMAL CONSTRUCTION STANDARDS AND LOCAL CODES AND PRACTICES. BEFORE STARTING CONSTRUCTION, THE CUSTOMER SHOULD CONSULT A CONTRACTOR OR ARCHITECT TO DETERMINE IF THE DRAWINGS NEED TO BE CHANGED TO SATISFY: 1.) STATE OR LOCAL BUILDING CODES OR REGULATIONS: 2.) PROJECTS STRUCTURAL REQUIREMENTS: 3.) EXISTING CONDITIONS SPECIFIC TO PROJECT OR PROJECT SITE. CONSULT LOCAL BUILDING OFFICIALS TO DETERMINE IF A BUILDING PERMIT IS REQUIRED. WE ASSUME NO RESPONSIBILITY FOR CLAIMS OR DAMAGES ARISING FROM ERRORS, OMISSIONS, DEFICIENCIES, IMPROPER CONSTRUCTION, OR DEFECTS OF THE DRAWINGS.

ACKNOWLEDGED BY: CUSTOMER/CONTRACTOR SIGNATURE _____ DATE


CONTRACTOR: BIGELOW HOMES
OWNER: HARVEST WEST MASTER PLAN #20-12

DRAWN BY:	MJP
DATE:	10/9/26
SQ. FT.	
SCALE:	NOTED
SHEET:	A05


BIGELOW HOMES



DETAIL 1
1/4"=1'-0"



DETAIL 4



DETAIL 3
1/4"=1'-0"

The dwelling separation shall be extended thru to exterior wall sheathing of perpendicular exterior walls and extend thru enclosed soffits and overhangs in attics.

BIGELOW HOMES
4057 28TH STREET NW #100
BUILDER LICENSE # BC-431673


THESE DRAWINGS HAVE BEEN PREPARED USING INFORMATION PROVIDED BY THE CUSTOMER/CONTRACTOR WHO IS SOLELY RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION PROVIDED. THE DRAWINGS ARE NOT A SUBSTITUTE FOR PERMIT DRAWINGS PREPARED BY A CONTRACTOR OR ARCHITECT AND MAY NOT MEET NORMAL CONSTRUCTION STANDARDS AND LOCAL CODES AND PRACTICES. BEFORE STARTING CONSTRUCTION, THE CUSTOMER SHOULD CONSULT A CONTRACTOR OR ARCHITECT TO DETERMINE IF THE DRAWINGS NEED TO BE CHANGED TO SATISFY: 1.) STATE OR LOCAL BUILDING CODES OR REGULATIONS; 2.) PROJECTS STRUCTURAL REQUIREMENTS; 3.) EXISTING CONDITIONS SPECIFIC TO PROJECT OR PROJECT SITE. CONSULT LOCAL BUILDING OFFICIALS TO DETERMINE IF A BUILDING PERMIT IS REQUIRED. WE ASSUME NO RESPONSIBILITY FOR CLAIMS OR DAMAGES ARISING FROM ERRORS, OMISSIONS, DEFICIENCIES, IMPROPER CONSTRUCTION, OR DEFECTS OF THE DRAWINGS.

ACKNOWLEDGED BY: CUSTOMER/CONTRACTOR SIGNATURE _____ DATE _____

CONTRACTOR: BIGELOW HOMES

OWNER: HARVEST WEST
MASTER PLAN #20-12

DRAWN BY: MJP
10/9/26
NOTED
NOTED
A04
BIGELOW HOMES



5547 SUNDOWN PLACE NW
ROCHESTER MN 55901
LOT 5, BLOCK 1, HARVEST WEST
HVW-001-051

STEM WALL
SEE DETAIL

5543 SUNDOWN PLACE NW
ROCHESTER MN 55901
LOT 6, BLOCK 1, HARVEST WEST
HVW-001-061

FOUNDATION PLAN
SCALE 1/4"=1'-0"

BIGELOW HOMES
4057 28TH STREET NW #100
BUILDER LICENSE # BC-431673

THESE DRAWINGS HAVE BEEN PREPARED USING INFORMATION PROVIDED BY THE CUSTOMER/CONTRACTOR WHO IS SOLELY RESPONSIBLE FOR THE ACCURACY OF THE INFORMATION PROVIDED. THE DRAWINGS ARE PREPARED PRIMARILY FOR PERMITTING PURPOSES AND ARE NOT A SUBSTITUTE FOR PERMIT DRAWINGS PREPARED BY A LICENSED ARCHITECT WHO IS FAMILIAR WITH LOCAL BUILDING CODES AND PRACTICES. BEFORE STARTING CONSTRUCTION, THE CUSTOMER SHOULD CONSULT A CONTRACTOR OR ARCHITECT TO DETERMINE IF THE DRAWINGS NEED TO BE CHANGED TO SATISFY 1.) STATE, 2.) COUNTY, 3.) CITY OR LOCAL BUILDING CODES OR ORDINANCES. IF A BUILDING PERMIT IS REQUIRED, CONSULT LOCAL BUILDING OFFICIALS TO DETERMINE IF A BUILDING PERMIT IS REQUIRED. FOR LARGE OR DAMAGED AREAS FROM ERRORS, OMISSIONS, DEFICIENCIES, IMPROPER CONSTRUCTION OR DEFECTS OF THE DRAWINGS.

ACKNOWLEDGED BY: CUSTOMER/CONTRACTOR SIGNATURE DATE

CONTRACTOR: BIGELOW HOMES
HARVEST WEST
MASTER PLAN #20-12
OWNER:

DRAWN BY:	MJP
DATE:	10/30/26
SQ. FT.	NOTED
SCALE:	NOTED
SHEET:	A02

BIGELOW HOMES